TUMKUR DIVISION.

ADVERTISEMENT.

The 28th November 1887.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 1st January 1888, for restoring the Handenhalli Tank, Sira Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1889.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Tumkur between the hours of 11 to 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for restoring the Handenhalli Tank, Sira Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Secretary, Public Works Department, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Detailed Abstract Estimate of restoring Handenhalli Tank, Registered No. of Sira Taluk.

Items of Work.	Per.	Quantity.	Rate.	Cost.
Bund.				
Earthwork	C. Yd.	131,394		
New stone work	do	6,257		
Old stone work	do	2,275		
Bench Mark stones	Each.	2		
Grade stones	do	41		
Excavation	C. Yd.	2,625		
Total.. .	..	..		
Sluices.				
2 Sluices	L. S	1,000		
Waste Weir.				
Excavation	C. Yd.	20,000		
Brick in chunam	C. Ft.	14,087		
Chunam plastering	Sq.	37·52		
Covering slabs	S. Ft.	938		
Total....	..	..		
Distribution.				
Sluice channel on both sides	L. S.	5,000		
Miscellaneous.				
Compensation of lands submerged	..	1,514		

C. T. DALAL,
Executive Engineer.

525

MYSORE DIVISION.

ADVERTISEMENTS.

The 28th November 1887.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 15th December 1887, for improving Narasambudhi tank, Registered No. 1, Nanjangud Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1889.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for improving Narasambudhi tank, Registered No. 1, Nanjangud Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Secretary, Public Works Department, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of Quantities.

Items of Work.	Per.	Quantity.	Rate.	Cost.	Total.
Earth excavation in soft earth	C. Yd.	6,420			
Do do in gravel	Do	3,606			
Do do rock ..	Do	282			
Do do embankments for channel.	Do	8,052			
Old stone revetment	Do	1,000			
New do	Do	1,710			
Brick in mortar	C. Ft.	7,899			
Slab stones	S. Ft.	215			
Plastering	Sq.	106			
Teakwood shutters	C. Ft.	18			
Archwork	Do	716			
Gravelling	C. Yd.	291			
Dismantling	C. Ft.	1,704			
Clearing jungle	Mile.	2½			
Grade stones for tank	Each.	75			
Do for channel	Do	132			
Index stones do	Do	84			
Do do	Do	48			
Mile stones	Do	6			
Furlong stones	Do	42			
Earthwork embankment for tank.. ..	C. Yd.	37,994			

The 28th November 1887.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 15th December 1887, for improving and extending Kemman Channel near Maddur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of January 1889.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement either in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 25 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for improving and extending Kemman Channel," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of Quantities.

Items of Work.	Per.	Quantity.	Rate.	Cost.	Total.
Excavation in soft earth	C. Yd.	5,711			
Do in mixture of gravel and earth ..	do	4,802			
Do in gravel	do	6,071			
Do soft rock and hard earth or gravel ..	do	226			
Embankment	do	57			
Brick in chunam	C. Ft.	2,300			
Plastering	Sqr.	1,400			
New stone work	C. Yd.	109			
Old do	do	67			
Rough stone in chunam	C. Ft.	11·50			
Slab stone	do	84			

V. H. KARVE, L. C. E.,
Executive Engineer.

KOLAR DIVISION.

ADVERTISEMENT.

The 1st December 1887.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 15th December 1887, for restoring Akkimangala Tank, Serial No. 566, in Chinta-

527.

mani Sub-Division. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1889.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Kolar between the hours of 11 A. M. and 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. —— in cash or Government promissory notes as earnest money and be superscribed "Tender for Akkimangala Tank, Serial No. 566, Ramasagara Series," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items.			*Quantity.*
Earthwork ..	.. Cubic Yards.	.. ..	29,700
Old stone work	.. do	.. ..	1,280
New stone work	.. do	.. ..	1,978
Grade stones ..	.. ..	.. ..	29
Bench Mark stones	.. ..	.. ..	2
Reg. No. stone	.. ..	.. ..	1
Gauge stone ..	.. ..	.. ..	1
Removing jungle	.. ..	.. .	..
Sluices 2. To be repaired as ordered.			
Weir.—Burnt brick in Surki chunam, Cubic Feet		.. ..	4,305
Chunam plastering	Square.	.. ..	20
Stone masonry	Cubic Feet.	.. ..	1,487
Archwork (stone)	Cubic Yards.	.. ..	471
Burnt slabs	Square Feet.	.. ..	247
Burnt stone sujikat	Cubic Yards.	.. ..	384

Y. SRINIVASA RAO,
Executive Engineer.

SHIMOGA DIVISION.

ADVERTISEMENT.

The 2nd December 1887.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 15th December 1887, for constructing a bridge over Varada River on Sagar-Siralkoppa road. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1889.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Shimoga between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government promissory notes, as earnest money and be superscribed "Tender for constructing a bridge over Varada River on Sagar-Siralkoppa road," in default of which tenders will be rejected."

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of Work.	Per.	Quantity.
Excavation cutting bank, soft laterite soil	C. Yd.	2,620
Do foundation do $\frac{1}{8}$ quantity	do	155
Do do do $\frac{2}{8}$ do . ..	do	311
Baling water	Lump sum.	..
Brick in surki mortar foundation	C. Ft.	9,916
Do ordinary mortar superstructure	do	15,175
Archwork do	do	1,913
Plastering with mortar	Sq.	67·54
Cornice work	R. Ft.	246
Centering	Each.	3
Guard stones	do	8
Earth filling	C. Yd.	5,042
Turfing	Sq.	198·26
Gravelling	C. Yd.	323
Rough stone work (new)	do	490

B. S. VENKATACHARIYAR,
Offg. Executive Engineer.

CIVIL AND MILITARY STATION, BANGALORE.

IN THE COURT OF THE CIVIL JUDGE.

Miscellaneous Application No. 335 *of* 1887.

In the matter of the estate of the late James Albert Brown .. *Deceased.*
Mrs. Margaret Amelia Michael (wife of J. R. Michael of Bangalore) .. *Applicant.*

Whereas Mrs. Margaret Amelia Michael, next of kin to the deceased above named, has applied to this Court for letters of administration to the property of the said deceased who died at Bangalore on the 4th day of August 1887, and Wednesday, the 21st day of December 1887, at 11 A. M., has been fixed for the hearing of the application.

All persons claiming to have any interest in the estate of the deceased are hereby called upon to come and see the proceedings, on or before the said Wednesday, the 21st day of December 1887.

Given under my hand and the seal of the Court this 5th day of December 1887.

H. M. S. MACRATH,
Civil Judge.